

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00778-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 9-17S-8W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: SHONYO Well #: 11  
County: ELLSWORTH Total Vertical Depth: 3274 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 5.5 feet: 3153  
SURF Size: 10.75 feet: 304

41  
106

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/29/2004 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
AUG 5 - 2004  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/29/2004 3:00 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Set CIBP @ 3000' and put 1-1/2 sacks of cement on top. Perforated at 1100', 700', and 350'. Ran tubing with packer to 1050' and pumped 35 sacks of cement. Pulled tubing to 650' and pumped 35 sacks of cement. Pulled tubing to 345' and circulated cement to surface.

Lost circulation at 345' after pumping nearly 400 sacks of cement. Came back on 7/30/2004 and ran tubing to 350'. Pumped approximately 120 sacks of cement and circulated to surface.

60/40 posmix with 4% gel.

RECEIVED  
AUG 05 2004  
KCC WICHITA

**Perfs:**

Top	Bot	Thru	Comments
3153	3170		

Remarks: ALLIED CEMENT #15208 (7/29/2004) & #15209 (7/30/2004)

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-16-04  
INV. NO. 2005060313