

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-20923-00-01  
Spot: W2NWNW Sec/Twnshp/Rge: 30-22S-9W  
4620 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SLEEPER Well #: 1-30  
County: RENO Total Vertical Depth: 3780 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3783 175 SX CMT  
SURF Size: 8.625 feet: 333 330 SX CMT

\$122<sup>85</sup>

Well Type: SWD UIC Docket No: D22481.0 Date/Time to Plug: 07/09/2004 12:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Sand to 2750' & 5 sxs; 1325' & 35 sxs; 850' & 35 sxs; 383' - 0'.  
Plugging Method:

RECEIVED  
KCC DISTRICT #2  
JUL 30 2004  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE  
Date/Time Plugging Completed: 07/09/2004 12:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 2750' and 5 sacks of cement. Cut the 5-1/2" casing off at 2150'. Pulled to 1325' and pumped 35 sacks of cement. Pulled to 850' and pumped 35 sacks of cement. Pulled to 380' and circulated to surface.

60/40 posmix with 4% gel.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 05 2004  
CONSERVATION DIVISION  
WICHITA, KS

Perfs:

Top	Bot	Thru	Comments
2828	2846		

Remarks: COPELAND CEMENT #24480

Plugged through: CSG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED

DATE

8-5-04

INV. NO.

2005060282