

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21893-00-00
Spot: N2SESE Sec/Twnshp/Rge: 16-30S-9W
990 feet from S Section Line, 540 feet from E Section Line
Lease Name: SWINGLE Well #: 1-16
County: KINGMAN Total Vertical Depth: 4320 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

SURF Size: 8.625 feet: 265

\$140⁴⁰

Well Type: OG DH UIC Docket No: _____ Date/Time to Plug: 07/02/2004 8:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: STEVE STEVENS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: Fill hole with heavy mud & spot cement through drill pipe. Spot 35 sxs. cement @ 1,425'. Spot 35 sxs. cement @ 975'. Circulate cement from 315' to the surface.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 07/02/2004 10:15 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report: _____ Perfs: _____

Filled hole with heavy mud. Spotted cement through drill pipe. Ran drill pipe to 1,425' and spotted 35 sxs. cement. Pulled drill pipe to 975' and spotted 35 sxs. cement. Pulled drill pipe to 310' and circulated 105 sxs. cement to the surface. Filled rat hole with 15 sxs. cement. Filled mouse hole with 10 sxs. cement.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 2004
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #2
JUL 8 - 2004
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING. INVOICE # 17831.

Plugged through: DP

District: 02 Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 7.28.04
INV. NO. 2005060200