

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20088-00-01
Spot: SESENW Sec/Twnshp/Rge: 27-30S-7W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: THOMAS SWD Well #: 4
County: KINGMAN Total Vertical Depth: 4953 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

PROD Size: 5.5 feet: 4850
SURF Size: 8.625 feet: 216

160 97

Well Type: SWD UIC Docket No: D16013.0 Date/Time to Plug: 06/04/2004 2:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: OH 4850' - 4953'. Packer and tubing stuck in hole at 4825' (R4 packer). Top of fish at 3035'.
Sand back to 2980' & 4 sxs; perf @ 1250' & 35 sxs; perf @ 700' & 35 sxs; perf @ 400 pump.

RECEIVED
KCC DISTRICT #2
JUL 1 - 2004
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/04/2004 5:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A sand plug was put at 2980' to cover the top of the fish. The sand was capped with 4 sacks of cement. The casing was perforated at 1250' and squeezed 35 sacks of cement. Top of cement 970'. Perforated at 700' and squeezed 35 sacks of cement. Perforated 430' and squeezed 70 sacks of cement. Shut in 400 lbs.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
4850	4953	OH	


RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE

7-28-04

INV. NO.

2005060205