

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22663-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 9-23S-14W
2970 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HARPER Well #: 2
County: STAFFORD Total Vertical Depth: 4052 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 4052 WITH 125 SX CMT
SURF Size: 8.625 feet: 445 WITH 215 SX CMT

\$131⁶⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2004 4:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3910' & 5 SX CMT. PLUG AT 890' WITH 10 SX GEL & 50 SX CMT. PLUG AT 490' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 07/26/2004 5:45 PM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3910' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 890' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 490' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3965	3972		

RECEIVED
AUG 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2310' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J Pfeifer
(TECHNICIAN)

INVOICED

DATE 8-5-04
INV. NO. 2005060312

Form CP 2/3
[Signature]