

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21344-00-01
Spot: NWNWSESE Sec/Twnshp/Rge: 15-33S-39W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: CHRISTOPHER A Well #: 1
County: STEVENS Total Vertical Depth: 6550 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 6025 WITH 2 SX CMT
PROD Size: 4.5 feet: 6547 WITH 350 SX CMT
SURF Size: 8.625 feet: 1677 WITH 350 SX CMT

\$ 212⁸⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/28/2004 1:00 PM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: CIBP @ 6000' WITH 10 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: NONE
Date/Time Plugging Completed: 07/28/2004 5:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 6470'. CASING LEAKS FROM 2600-3780'. SET CIBP @ 6025' WITH 2 SX CMT ON TOP WITH TUBING. PULL OUT OF HOLE TO 3800', CIRCULATE HOLE. PUMP 135 SX CMT AT 3800' TO PLUG CASING LEAKS. PULL OUT OF HOLE WITH TUBING TO 2000'. LOAD HOLE. STAYED FULL. PULL OUT OF HOLE WITH TUBING & LAY DOWN. RUN IN HOLE WITH RIPPER. GOT STUCK AT 150'. BACK OFF 4 1/2" CASING AT 1700'. PULL OUT OF HOLE & LAY DOWN JOINT WITH RIPPER. RUN BACK IN HOLE WITH CASING TO 1700'. LOAD HOLE & PUMP 95 SX CMT. PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 50 SX CMT. PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
6100	6108		
6089	6097		
6075	6079		

RECEIVED
AUG 05 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 1700' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

[Signature]
(TECHNICIAN)

INVOICED

DATE 8-5-04
INV. NO. 2005060281

[Signature]
Form CP 2/8