

4-032418

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-137-00,575-0000

NW NW SE /4 SEC. 30, 03, 23 W  
2310 feet from S section line  
2310 feet from E section line

Operator license# 5285

Lease: Weber Well # 1-3

Operator: D.G. Hansen Trust

County: Norton

5/18

121.78

Address: P.O. Box 187  
Logan, Kansas 67646-0187

Well total depth 3747 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 249 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Murfin Drilling Company License# -

Address: Hill City, Kansas 67642

Company to plug at: Hour: A.M. Day: 18 Month: May Year: 2000

Plugging proposal received from: Rich Wallgren

Company: D.G. Hansen Trust Phone: -

Were: Order 300 sxs 60/40 pozmix - 10% gel - 400# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

Allied Cement Company.

Order work string.

JUN 1 2000

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:30 A.M., Day: 18 Month: May Year: 2000

Actual plugging report: 8 5/8" set at 249' w/170 sxs cwc. 5 1/2" set at 3745' w/125 sxs.  
Prod O.H. 3744' - 3747'. P.B.T.D. 3667'. State ordered bottom sanded back to 3650' for T.A.  
Ran tubing to 1800'. Mixed and pumped 145 sxs cement blend to circulate. Squeezed 8 5/8"  
with 75 sxs cement blend to Max. P.S.I. 300#. Plug complete.

Remarks:

Condition of casing (in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug (in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

INVOICE

DATE 6/6/00

INV. NO. 61825

Form CP-2/3