

6 030700

15-137-00574-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- ~~1954~~

GEL SE, SEC. 30, T. 3 S, R. 23 W/2

1320 feet from S section line

0 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258 5285

Lease Name WEBER Well # 12

Operator: D.G. HANSEN TRUST

County NORTON 122.92

Name & Address Box. 187

Well Total Depth 3782' feet

LOGAN, KANSAS

Conductor Pipe: Size _____ feet

67646

Surface Casing: Size 8 5/8 feet 303'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: P.M. Day: 27 Month: 3 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING. (phone) _____

were: 8 3/8 @ 303' w/200sx. 5 1/2 @ 3779' w/125sx. ORDER SAND & COM. CMT. SHOOT & RECOVER PIPE. ORDER 180sx. 60/40. P02 6% GEL 3% cc 40sx. GEL. 4sx. HULLS W.P. ALLIED CMT. Co.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45PM Day: 27 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3700' SPOT 5sx. COM CMT ON SAND W/BAILER. SHOT & RECOVERED 1002' OF 5 1/2"

MIX. & Pump DOWN 8 5/8 3sx. HULLS 26sx. GEL. 100sx. CMT. MIX. + 1sx. HULLS 14sx. GEL. 80sx. CMT MIX. MAX. PSI 200* CLOSE IN 150*
Plug COMPLETE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 15 1986

INV. NO. 13442

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

4-13-86

Signed Carl Goodnow
(TECHNICIAN)

15
4-11-86