

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - (7-21-1954)

C E 2 N 1/2 Sec. 31, T 3 S, R 23 (W) 4

— feet from N/S section line

— feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Mindrop Well # 8

Operator: John O. Farmer
Name &
Address P.O. Box 352
Russell, Kansas
67662

County Norton

Well Total Depth 3680 feet 119.60

Conductor Pipe: Size — feet —

Surface Casing: Size 8 5/8 feet 280'

Abandoned Oil Well X Gas Well — Input Well — SWD Well — D&A —

Other well as hereinafter indicated —

Plugging Contractor Altied Cementing License Number —

Address Russell, Kansas

Company to plug at: Hour: 4:45pm Day: 13 Month: 2 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Mr. Eichmann

(company name) John O. Farmer (phone) —

were: 5 1/2" csg set @ 3674' w/75 sk cmt.

Ordered 275 sk 5% poly 10% gel 3% cc + 5 1/2" W. Plug

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part — None —

Operations Completed: Hour: 4:45pm Day: 13 Month: 2 Year: 1984

ACTUAL PLUGGING REPORT

Rmptd in 5 1/2" csg -> 15 sk cmt w/hull -> 18 sks gel
w/1 sk hull -> R. Plug -> 100 sk cmt. -> 500# P.S.I.
Rmptd in 1 sk hull -> 2 sks gel -> 50 sks cmt -> 3 sks gel ->
60 sks cmt @ 750# P.S.I. come back
next day & capped well w/45 sk

Remarks: —

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 4-5-84

INV. NO. 10070

RECEIVED
STATE CORPORATION COMMISSION

APR 02 1984

CONSERVATION DIVISION
Wichita, Kansas

4-2-84