

4-031662

2-21

9R

15-137-00576-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1954

C SW /4 SEC. 30, 03 S, 23 W  
1320 feet from S section line  
3960 feet from E section line

Operator license# 5285

Lease Weber well # 13

Operator: The Dane G. Hansen Trust

County Norton

Address: Box 187  
Logan, Kansas 67646

Well total depth 3672 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 218 feet

119.34

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 21 Month: February Year: 92

Plugging proposal received from: Rich

Company: Hansen Trust Phone:                     

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
8 5/8" set @ 218' w/120 sx. 5 1/2" set @ 3669' w/125 sx.  
Perf. 3668' - 72'. Hole open across perf's.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

3-9-92  
Kansas

Completed: Hour: 10:30A.M., Day: 21, Month: February, Year: 1992

Actual plugging report: Shots @ 1930' anhy. and 1150' Kiowa.  
Squeezed 5 1/2" casing w/350 sx. cement blend w/400# hulls mixed in to  
Max. P.S.I. 600#. Close in P.S.I. 400#. Squeezed 8 5/8" w/100 sx.  
cement w/100# hulls mixed into Max. P.S.I. 500#. Close in P.S.I. 200#.  
Plug complete.

Remarks: Cement from 3672' to surface across and into anhy.  
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC    , NO     Dakota plug: YES    , NO      
Plugged through TUBING    , CASING    . Elevation: 2346 GL

INVOICED [ ] did not [ ] observe the plugging. Carl Goodrow

DATE 3-16-92  
INV. NO. 34744

MD

(agent)  
Form CP-2/3