

6 030699

15-137-00562-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA 1967

NWNWSW SEC. 30, T. 3 S, R. 23 (W)

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258 5285

Lease Name WEBER Well # 2

Operator: D.G. HANSEN TRUST

County NORTON 119.31

Name & Address Box 187

Well Total Depth 3671' feet

LOGAN, KANSAS

Conductor Pipe: Size _____ feet

67646

Surface Casing: Size 8 3/8 feet 254'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 27 Month: 3 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING. (phone) _____

were: 8 3/8 @ 254' w/160 SX. 5 1/2 @ 3668' w/125 SX. PBT D 3645' TOP PER F 3512'
ORDER SAND & CON. CMT. SHOOT & RECOVER PIPE ORDER 180 SX. 60/40 P2
6 GEL 3 PCC 40 SX. GEL 4 SX. HULLS ALLIED CMT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 PM Day: 27 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBT D TO 3460 SPOT 5 SX. CONCENT. ON SAND

SHOT & RECOVERED 1021' OF 5 1/2"

MIX. & Pump DOWN 8 3/8 3 SX. HULLS 26 SX. GEL. 100 SX. CMT. MIX. + 1 SX.

HULLS 14 SX. GEL. W.P. 80 SX. CMT. MIX. MAX. PST 500# CLOSE IN 200#

PLUG. COMPLETE

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 15 1986

INV. NO. 13441

RECEIVED STATE CORPORATION COMMISSION

APR 13 1986

CONSERVATION DIVISION Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

4-13-86

15 4-11-86