

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20669-00-00
Spot: NESE Sec/Twnshp/Rge: 25-34S-35W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: KINNEY CHESTER SAND UNI Well #: 602
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

CIBP Size: feet: 5675 WITH 2 SX CMT
COND Size: 21 feet: 20 WITH 3 YDS CMT
PROD Size: 5.5 feet: 6760 WITH 175 SX CMT
SURF Size: 8.625 feet: 1641 WITH 775 SX CMT

#219³⁸

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/04/2004 3:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 300# HULLS. PLUG AT 1700' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/05/2004 11:00 AM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:


PBTD 6713'. CIBP @ 5675' WITH 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1700'. LOAD HOLE & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH CASING TO 600'. SDON. 08/05/04: LOAD HOLE WITH MUD & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Top	Bot	Thru	Comments
6503	6515		

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2333' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN)

INVOICED

DATE

8-11-04

TW. NO.

2005060343

RECEIVED

AUG 12 2004

KCC WICHITA

Form CP 2/3