

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-01136-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 2-21S-11W  
1650 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: RUGAN D Well #: 1-2  
County: STAFFORD Total Vertical Depth: 3386 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL, SUITE 100  
WICHITA, KS 67206

PKR Size: feet: 3271  
PROD Size: 4.5 feet: 3420 WITH 165 SX CMT  
SURF Size: 8.625 feet: 285 WITH 200 SX CMT

\$110<sup>05</sup>

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/05/2004 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 2919' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/05/2004 12:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PACKER LEFT IN HOLE @ 3271'. ANHYDRITE @ 467'. SANDED TO 2919' & 4 SX CMT WITH BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3374	3379		
3311	3338		
3293	3298		
3006	3014		

RECEIVED  
AUG 10 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1620' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 8-10-04

INV. NO. 2005060338

Form C-11/3