

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23029-00-00
Spot: SESENE Sec/Twnshp/Rge: 4-21S-11W
2950 feet from S Section Line, 330 feet from E Section Line
Lease Name: RUGAN F Well #: 1-4
County: STAFFORD Total Vertical Depth: 3450 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

CIBP Size: feet: 3407
PROD Size: 5.5 feet: 3447 WITH 200 SX CMT
SURF Size: 8.625 feet: 275 WITH 250 SX CMT

112¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3280' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2004 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 511'. SANDED TO 3281' & 5 SX CMT WITH DUMP BAILER.
SPOOTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3362	3368		
3350	3356		
3343	3348		
3339	3341		

RECEIVED
AUG 10 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2010' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
AUG - 6 2004
KCC Dodge City

INVOICE

DATE 8-10-04

INV. NO. 2005060338

Form CR-2/3