

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21545-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 5-14S-15W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DORTLAND C Well #: 1
County: RUSSELL Total Vertical Depth: 3307 feet

Operator License No.: 6772
Op Name: WEIGEL, V. FRANCIS - FAMILY PARTN
Address: PO BOX 219
GORHAM, KS 67640

PROD Size: 5.5 feet: 3305 135 SX CMT
SURF Size: 8.625 feet: 675 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2004 10:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: WEIGEL, V. FRANCIS-FAMILY PA Phone: (785) 483-3854

Proposed Plugging Method: Ordered out 330 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2004 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1580' and 965'.
TIH with tubing to 1600' - mixed and pumped 225 sxs cement with 600# hulls.
Pulled up to 600' - circulated cement up 5 1/2" with 25 sxs cement.
POOH. Swaged onto 5 1/2" and circulated cement up 8 5/8".
Shut in and pumped 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3227	3230		
3124	3128		
3069	3072		

RECEIVED
AUG 06 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-6-04

TEL. NO. 2005060324

AUG 04 2004

V FRANCIS WEIGEL

BOX 244

GORHAM, KS 67640

#1 "C" DORTLAND APPX C N/2 N/2 NW 5-14-15W

CONTR SHIELDS DRILLING CO CTY RUSSELL

GEOL FRANCIS WHISLER FIELD GORHAM

E 1885 KB CM 9/29/80 CARD ISSUED 6/18/81 IP P 4 BO & 100 BWPD

API 15-167-21,545

LKC-INTV NA

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
TOP		2768	- 883
HEEB		2992	-1107
TOR		3012	-1127
LANS		3042	-1157
*B KC		3285	-1400
*GRAN WSH		3290	-1405
LTD		3283	-1398
RTD		3307	-1422
*SMP TOPS			

8-5/8" 675/375sx, 5 1/2" 3305/135sx

NO DST'S
MICT - CO, PF (LKC) INTV NA, TSTD
SO, POP, TIGHT HOLE - NO OTHER INFO
TO BE RELEASED BY OPERATOR

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS