

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00578-00-00
Spot: CNENESE Sec/Twnshp/Rge: 30-3S-23W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: WEBER Well Number: 11
County: NORTON Total Vertical Depth: 3798 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 307 200 SX CMT
Production: Size 5.5 feet: 3796 125 SX CMT
Liner: Size feet:

\$123.44

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/18/2001 9:00 AM
Plug Co. License No.: 5285 Plug Co. Name: HANSEN, DANE G. - TRUST
Proposal Rcvd. from: RICHARD WALLGREN, SR. Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Order 310 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/18/2001 10:35 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 307' w/200 sxs cwc. 5 1/2" set at 3796' w/125 sxs.
5 1/2" squeezed with 1080 sxs from 3036' to surface with bad casing.
Fluid Level at 3200'. O.H. 3796' - 3800'.
Squeezed 5 1/2" with 260 sxs cement blend with 200# hulls mixed in to Max. P.S.I. 600#. Held.
Squeezed 8 5/8" with 50 sxs to Max. P.S.I. 100#.

RECEIVED
JAN 03 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 01-03-02

INV. NO. 2002061164


DEC 27 2001

D G HANSEN #11 WEBER 30-3-23W
 NE NE SE
 Contr. C-G DRLG NORTON County
 E 2470 RB Comm. Comp. 1-28-55 IP 1.08 BOPD
 PHY POT

Tops	Depth	Datum
HEEB	3520	-1050
TOR	3544	-1074
KC	3560	-1090
B/KC	3711	-1271
ARB	3795	-1325
ID	3798	-1329

Casing
 8" 307
 5" 3796
 CO 3799: 4 BOPH

NORTON POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS