

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02839-00-00
Spot: NESENE Sec/Twnshp/Rge: 5-9S-24W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: HOLLEY Well #: 15-2
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 30420
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR
Address: 30-38 48TH STREET
ASTORIA, NY 11103

PROD Size: 5.5 feet: 4040 150 SX CMT
SURF Size: 8.625 feet: 255 200 SX CMT

#131³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/05/2004 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES, INC. Phone: (785) 625-8360

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
Tubing stuck at 3500'. Backed tubing off at 3400'.
Alt. II. DV at 2145' w/275 sxs cement.
Fluid level at 450'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2004 1:40 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2100'.
Allied pumped 50 sxs neat, followed with 125 sxs cement with 300# hulls - cement circulated.
PTOH. Allied squeezed with 135 sxs cement with 100# hulls.
Max. P.S.I. 1000#. S.I.P. 600#.
Hooked up to backside. Allied pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3800	3974		

RECEIVED
AUG 10 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS KEITH #B-2.

Plugged through: TBG

District: 04

Signed

Richard Williams

INVOICED

8-10-04

2005060340

Form CP-2/3

AUG 09 2004

5-9-24W

KAISER & FRANCIS O & G #2 KEITH 'B' APP NE SE NE

Contr. _____ GRAHAM County

E 2485^{RE} Comm. _____ Comp. 12-16-55 IP 240 BOPD

Tops	Depth	Datum
HEEB	3780	-1295
TOR	3810	-1325
LANS	3820	-1335
TD	4040	-1555

Casing
 8" 255
 5" 4040 CORRECTED CARD
 12-30-55

PERF 3969-74:ACID 1500
 1 BOPH

HOLLY NW POOL (CORR PERFS)

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS