

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

** Approx. 90W & 45N of

Lease Operator: Lario Oil & Gas Company
Address: 301 S. Market St.; Wichita, KS 67202
Phone: (316) 265-5611 Operator License #: 5214
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/13/2004 (Date)
by: Herb Deines - Hays (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-22980-00-00
Lease Name: Worcester
Well Number: 1-26
Spot Location (QQQQ): ** - N2 - SW - SW
1035 Feet from North / South Section Line
570 Feet from East / West Section Line
Sec. 26 Twp. 7 S. R. 25 East West
County: Graham
Date Well Completed: 06/13/2004
Plugging Commenced: 06/13/2004
Plugging Completed: 06/13/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	281'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 200 sks 60/40 (Poz)+6% Gel + 1/4# flocele as follows:

1st plug - 25 sks @ 2175'; 2nd plug - 100 sks @ 1425'; 3rd plug - 40 sks @ 325'

top plug - 10 sks @ 40' to surface; Rat hole - 15 sks; Mouse hole - 10 sks

Name of Plugging Contractor: Allied Cementing Co. VonSeldt Drilling Inc License #: 9431 **RECEIVED**
Address: P.O. Box 31; Russell, KS 67665 **AUG 10 2004**
Name of Party Responsible for Plugging Fees: Lario Oil & Gas Co. **KCC WICHITA**
State of Kansas County, Sedgwick, ss.

Jay G. Schweikert, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jay G. Schweikert
(Address) 301 S. Market St.; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 9 th day of August, 20 04
Kathy L Ford My Commission Expires: 10-22-06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials