

15-137-00567-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Weber

WELL NUMBER #8

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line  
NE NE ~~SE~~ SW

SEC. 30 TWP. 3 RGE. 23W (E) or (W)

COUNTY Norton

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-16-86

Plugging Completed 12-19-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Dane G. Hanson Trust

ADDRESS P.O. Box 187 Logan, Kansas 67646

PHONE#( 913 ) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	260'	none
				5-1/2"	3717'	797'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3620' and 5 sacks cement. Shot pipe @1200', 1000', 797', pulled a total of 25 joints of 5-1/2" casing. Plugged surface with 5 sacks hulls and 200 sacks econolite. Plugging Complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. **DEC 30 1986**  
CONSERVATION DIVISION

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso  
(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 86

Jane Jones  
Notary Public

My Commission Expires: 