

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-137-00564-00-00

API NUMBER Spud 3/3/54

LEASE NAME Weber

WELL NUMBER #4

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 30 TWP. 3 RGE. 23 (X) or (W)

COUNTY Norton

Date Well Completed 3/11/54

Plugging Commenced 3:30 P.M. 4/20/93

Plugging Completed 4:30 P.M. 4/20/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 20, 1993 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top \_\_\_\_\_ Bottom T.D. 3741

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	247'	None
				5 1/2"	3740'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Down 5 1/2" casing mixed 5 sks. hulls with 250 sx cement. Max. press. 900%,  
Shut in 300%. Down 8 5/8" casing, mixed 100 sx. cement. Max press. 300%.  
Shut in 150%.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc./ License No. \_\_\_\_\_

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales (Employee of Operator) or (~~Operator~~) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Rec'd  
4-26-93

(Signature) [Signature]

(Address) Dane G. Bales  
P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 21 day of April, 1993



[Signature]  
Notary Public Betty Jane Bittel

My Commission Expires: July 17, 1996.

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Weber #4  
 LOCATION SE SE SW, SEC. 30-3-23W,  
 POOL NAME Norton COUNTY Norton STATE Kansas  
 COMMENCEMENT DATE March 3, 1954 COMPLETION DATE March 11, 1954

LOG OF WELL

Elevation: 2386 R.B.  
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	247	Shale		RECEIVED MAY 31 1954 D. G. Hansen, BY.....
247	400	Shale		
400	945	Shale		
945	1045	Sand		
1045	1400	Shale-Sand	0° - 1500'	
1400	1615	Shale-Sand		
1615	1735	Sand		
1735	1975	Red Bed		
1975	1980	Anhydrite	0° - 2000'	
1980	2016	Anhydrite		
2016	2265	Shale	0° - 2500'	RECEIVED MAY 31 1954 D. G. Hansen, BY.....
2265	2510	Shale-Lime		
2510	2665	Shale-Shells		
2665	2850	Lime-Shale		
2850	2970	Lime-Shale	0° - 3000'	
2970	3100	Shale-Lime		
3100	3230	Lime-Shale		
3230	3375	Lime-Shale		
3375	3450	Shale-Lime	0° - 3500'	
3450	3508	Lime-Shale		
3508	3580	Lime-Shale		
3580	3663	Lime-Shale		
3663	3701	Lime-Shale		
3701	3715	Shale		
3715	3738	Lime-Shale		
3738	3741	Lime-Shale		Core 3713
3741	3741	TD		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 247.01 (8 jts) 8-5/8" Surface Casing.  
 Ran 3762.29' (118 jts) 5-1/2" OD Casing.

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Wicky Jacobs Office Manager

Subscribed and sworn to before me this 27th day of May, 1954.

Barbara D. ...  
 PUBLIC NOTARY COMMISSION

My commission expires: June 17, 1957

APR 26 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas