

15-137-00562-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Weber

WELL NUMBER # 2

SPOT LOCATION NW NW SW

SEC. 30 TWP. 3 RGE. 23W (E) or (W)

COUNTY Norton

Date Well Completed _____

Plugging Commenced 3-20-86

Plugging Completed 3-27-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Dane G. Hansen Trust

ADDRESS Box 187 Logan, Kansas 67646

PHONE # (913) 689-4816 OPERATORS LICENSE NO. 5285
5258

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3671'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	254'	none
				5-1/2"	3668 1/2'	1032'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged off bottom with sand to 3450' and 5 sacks cement. Shot pipe @1620', 1429', 1210', 1032' and pulled a total of 33 joints (1032') of 5-1/2" casing. Plugged surface with 26 gel w/3 hulls, 100 cement w/1 hull, 14 gel, wiper plug and 89 cement, 60/40 pos, 6% gel, 3% cc. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks.. 67524

SUBSCRIBED AND SWORN TO before me this 31 day of March, 1986

My Commission expires: _____



RECEIVED [Signature]
STATE CORPORATION COMMISSION Notary Public

APR - 1 1986 4-1-86

CONSERVATION DIVISION