

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Vincent Oil Corporation
Address: 125 N Market ST 1075, Wichita, KS 67202-1721
Phone: (316) 262-3573 Operator License #: 5004
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L.K.C. Depth to Top: 4314 Bottom: 4319 T.D. 4584

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-20893-00-00
Lease Name: Fruit
Well Number: 4
Spot Location (QQQQ): C - SW - SW - NW
2970 Feet from North / South Section Line
4950 Feet from East / West Section Line
Sec. 19 Twp. 27 S. R. 15 East West
County: Pratt
Date Well Completed: 22 8-9-04
Plugging Commenced: 7-21-04
Plugging Completed: 7-22-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	367	
				5 1/2 14	4584	3000'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole sand at 4251', bailed 5 sacks, ripped 3200', 3000', pulled 1000', pumped 50 sacks, pulled 390', pumped 50 sacks, pulled to 40', pumped 10 sacks.


RECEIVED
AUG 09 2004

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of KANSAS County, SEDGWICK, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) Richard A. Hiebsch
(Address) 126 N. Market, Suite 1075, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 6th day of August, 2004

Yolanda Eubanks My Commission Expires: _____
Yolanda Eubanks Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas.

ALLIED CEMENTING CO., INC.

15341

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
MEDICINE CREEK

DATE <i>7-22-04</i>	SEC. <i>19</i>	TWP. <i>21S</i>	RANGE <i>15W</i>	CALLED OUT <i>11:00 AM</i>	ON LOCATION <i>1:30 PM</i>	JOB START <i>3:00 PM</i>	JOB FINISH <i>5:00 PM</i>
LEASE <i>FRUIT</i>	WELL # <i>4</i>	LOCATION <i>FRATT/KIOWA Co. LINE ON</i>			COUNTY <i>FRATT</i>	STATE <i>KANSAS</i>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<i>54, 4 1/2 N, E/SOUTH INTO</i>					

CONTRACTOR *QUALITY W-S* OWNER *VINCENT OIL*

TYPE OF JOB *OHP*

HOLE SIZE *7 7/8"* T.D. _____

CASING SIZE *8 1/8"* DEPTH *367'*

TUBING SIZE *5 1/2"* DEPTH *1000'*

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT *18 BBLs. FRESH WATER*

EQUIPMENT _____

PUMP TRUCK # *343* CEMENTER *KEVIN BRUNGARDT*

BULK TRUCK # *242* HELPER *MATCH WELLS*

BULK TRUCK # _____ DRIVER *MIKE RUCKER*

BULK TRUCK # _____ DRIVER _____

CEMENT

AMOUNT ORDERED *10 SK GEL*

110 SK 60:40:6

COMMON <i>14</i>	<i>66</i>	@	<i>7.65</i>	<i>504.90</i>
POZMIX	<i>44</i>	@	<i>4.00</i>	<i>176.00</i>
GEL	<i>16</i>	@	<i>11.00</i>	<i>176.00</i>
CHLORIDE		@		
		@		
		@		
		@		
		@		
HANDLING	<i>126</i>	@	<i>1.25</i>	<i>157.50</i>
MILEAGE	<i>126</i>	X	<i>20</i>	<i>.05</i>
				<i>126.00</i>
				TOTAL <i>1140.40</i>

REMARKS:

Good Hole / 10 SK GEL
SPOT 50 SK @ 1000'

Good Hole
SPOT 50 SK @ 390'

Good Hole - BEACONATE CEMENT TO SURFACE FROM 40' / 10 SK

SERVICE

DEPTH OF JOB *1000'*

PUMP TRUCK CHARGE _____ *500.00*

EXTRA FOOTAGE _____ @ _____

MILEAGE *20* @ *4.00* *80.00*

PLUG _____ @ _____

_____ @ _____

_____ @ _____

TOTAL *580.00*

CHARGE TO: *VINCENT OIL*

STREET *125 N. MARKET, ST. 1075*

CITY *WICHITA* STATE *KANSAS* ZIP *67202*

FLOAT EQUIPMENT

RECEIVED _____ @ _____

AUG 09 2004 _____ @ _____

KCC WICHITA _____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE ~~1140.40~~

DISCOUNT ~~1140.40~~ IF PAID IN 30 DAYS

SIGNATURE *[Signature]*

PRINTED NAME

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING