

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

6/05

API # 15 - 065-01471-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: VESS OIL CORPORATION (Owner / Company Name) KCC License #: 5030 (Operator's)

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita

State: KS Zip Code: 67226 Contact Phone: (316) 682 - 1537 X103

Lease: Morel B Well #: 8 Sec. 22 Twp. 9S S. R. 21 East West

SE - SW - NE Spot Location / QQQQ County: Graham

2310' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 234' Cemented with: 175 Sacks

Production Casing Size: 5-1/2 Set at: 3780' Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3780-81 DV-1753 w/394 sx

Elevation: 2286 (G.L. / K.B.) T.D.: 3781' P.B.T.D.: 3781' Anhydrite Depth: 1785'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): in accordance with KCC rules and regulations

RECEIVED

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

AUG 09 2004

If not explain why? NA

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Joel Stull

Phone: (785) 483 - 9169

Address: P.O. Box 307 City / State: Natoma, KS 67651

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665-0031 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): as soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/4/04 Authorized Operator / Agent: WR [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WELL RECORD

Company..... Cities Service Oil Company Well No. 8 Farm Moral "B"
 Location..... 330' North and 990' E. of Center Sec. 22 T. 9 R. 21W
 Elevation..... 2286 (2284 Gr.) County..... Graham State..... Kansas
 Drlg. Comm. December 28, 1951 Contractor..... R. W. Rine Drilling Company
 Drlg. Comp. January 5, 1952 Acid..... None
 T. D..... 3781' Initial Prod. Physical Potential: 156 oil, 40% water, 24 hrs. (3-10-52)

CASING RECORD:

8-5/8" @ 234' con. 175 sz cement
 5-1/2" @ 3780' con. 175 sz cement and
 D-7 tool at 1753' with
 350 sz cement and 44 sz
 Stratacrete.

FORMATION RECORD:

surface clay & sand	0-40
sand, clay & shale	234
shale	600
shale & shells	1425
shale	1730
anhydrite	1785
shale & shells	2150
shale, shells & lime	2385
shale & lime	2525
shale & broken lime	2730
shale & lime	2850
lime & shale	3375
lime	3654
lime & shale	3762
lime	3783

3783 RTD = 3781 SLM

Corr. Hooker	3443'
Corr. Dodge	3469'
Corr. Lansing	3482'
Corr. Simpson	3766'
Corr. Arbuckle	3779'
Penetration	2'
Total Depth	3781'

Fillup: 60' oil in 20 mins.
 95' oil in 30 mins.
 1066' oil in 1 hr. 30 mins.
 1342' oil in 2 hrs.

1-17-52 Pumped 116 oil, 13 water,
 24 hrs.

SYFO: 500' 2°
 1000' 1°
 1500' 2°
 2000' 1°
 2500' 1°
 3000' 1°
 3500' 0°

7-7/8" rotary hole.

3-11-52 G.O. To bottom

RECEIVED
AUG 09 2004
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Vess Oil Corporation
8100 E. 22nd N. Bldg. 300
Wichita, KS 67226

August 10, 2004

Re: MOREL B #8
API 15-065-01471-00-00
SESWNE 22-9S-21W, 2310 FNL 1650 FEL
GRAHAM COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely


David P. Williams
Production Supervisor