

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-30086-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 - 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
12-1-70

*NIXON*

Operator's Full Name R. P. Nixon Operations, Incorporated.

Complete Address 75 1/2 East Wichita Avenue, Russell, Kansas.

Lease Name Horesky Well No. 1

Location NW-SW-NE Sec. 29 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3816'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. 637

Operation Completed: Hour 12:00 M Day 23 Month 11 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3812'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to  
3700'. Top perforations @ 3677'.

Sanded well back to 3650' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well initially with 3 sacks hulls and 13 sacks gel and followed with 100  
Sx. cement from 1100' to 775' then 1 1/2 sacks gel from 775' to 225' and followed with  
25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx.  
cement from 30' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in  
pressure-200#. (Mudding and cementing operations by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. S. Nichols  
Well Plugging Supervisor

DATE 12/1/70  
INV. NO. 2946-w