

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 10 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

10-10-78

API Number 15 - 147 20,245-0000 (of this well)

Operator's Full Name Petroleum Management, Inc.
 Complete Address 400 N. Woodlawn, Suite 201, Wichita, Kansas
 Lease Name Emma Well No. 2
 Location NE NE SE Sec. 35 Twp. 3 Rge. (E) (W) 19
 County Phillips Total Depth 2282'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
 Other well as hereafter indicated
 Plugging Contractor Pioneer Drlg.
 Address Plainville, Kansas License No.
 Operation Completed: Hour 7:15 P Day 6 Month 10 Year 1978

The above well was plugged as follows:

RTD 2282' 8 5/8 csg set 206' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 900' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 10-12-78

INV. NO. 8276-W