

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20059-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1970
CONSERVATION DIVISION
Wichita, Kansas
7-14-70

Operator's Full Name Dreiling & Hiko Bell

Complete Address Victoria, Kansas

Lease Name Heaton "B" Well No. 1

Location ~~SW~~ NW-SW Sec. 23 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3755

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4:45 P Day 12 Month 7 Year 1970

The above well was plugged as follows:

RTD 3755' 8 5/8 csg set at 287' cwc Cmt. Mat. 100 sk reg poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 1250' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/70
INV. NO. 2227-W

Signed: Leo F. Massey
Well Plugging Supervisor