

KANSAS

RP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20029-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas
7-14-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company.

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Heaton Well No. 1

Location CNW-SE Sec. 23 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3792'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated.

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 1:30 AM Day 8 Month 7 Year 1969

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from 275'
to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/69

INV. NO. 84-W

Signed: *W. S. Nichols*
Well Plugging Supervisor