

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-137-00703-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 45-25

LOCATION QW¹ SW

SEC. 31 TWP. 3 RGE. 23

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease Garr Sneed

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Norton

Total Depth 3789 Feet.

Plugging Contractor Forbes Casing Pulling & Globe Cementing Co

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 295' circulated with cement - 5 1/2" at 3785' with 75 sax
cement behind.

Filled with chat to 3770', set ~~xx~~ 4 sax cement with dump bailer,

pulled 1850' 5 1/2" to 1000', circulated hole with heavy mud at 1000'

(commercial mud) displaced 25 sax cement through 5 1/2" at 650', heavy

mud to 270', displaced 20 sax cement through 5 1/2" at 270', heavy mud

to 35', set rock and 10 sax cement to bottom cellar.

Mudding and Cementing By Globe Cementing Co.

Eason Lee
District Conservation Agent

Date 9-13-57

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1957

CONSERVATION DIVISION
Wichita, Kansas

9-23-57

PLUGGING
FILE SEC 31 T 3 R 23W
BOOK PAGE 45 LINE 25