

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-137-00730-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 45-24

LOCATION CN $\frac{1}{2}$ SW

SEC. 31 TWP. 3 RGE. 23

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Carr Sneed

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Norton

Total Depth 3757 Feet.

Plugging Contractor Forbes Casing Pulling and Globe Cementing Co

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 280' circulated with cement - 5 1/2" at 3735' with 75 sax
cement behind.

Filled with sand to 3720', set 4 sax cement with dump bailer, pulled
1757' 5 1/2" to 1200', circulated hole with heavy commercial mud through
5 1/2" - displaced 20 sax cement through 5 1/2" at 650', heavy mud to 270',
displaced 20 sax cement through 5 1/2" at 270', set 20 sax cement at
200', heavy mud to 35', set cementing plug, 1/2 sack hulls and 10
sax cement to bottom cellar - Mudding and Cementing by Globe Cementing Co

Edward L. Kelly
District Conservation Agent

Date 9-18-57

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1957
CONSERVATION DIVISION
WICHITA, KANSAS

9-23-57

PLUGGING
FILE SEC. 31 T. 3 R. 23W
BOOK PAGE 45 LINE 24