

R

DISTRICT CONSERVATION AGENT'S REPORT

15-137-00729-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 45-23
LOCATION NW NW SW SW
SEC. 31 TWP. 3 RGE. 23

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Carr Sneed

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Worton

Total Depth 3773 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 280' circulated with cement - 5 1/2" 3771' with 75 sax cement.
Filled with sand to 3755', set 4 sax cement with dump bailer, pulled
1600' ~~xxxxx~~ 5 1/2" to 1100' circulated hole with heavy commercial mud
through 5 1/2" at 1100', displaced 20 sax cement through 5 1/2" at 650',
heavy mud to 270', displaced 20 sax cement through 5 1/2" at 270', heavy
mud to 35', set rock and 10 sax cement to bottom cellar.

Mudding and Cementing by Globe Cementing Co.

Edwin Peely
District Conservation Agent

Date 9-16-57

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1957
CONSERVATION DIVISION
Wichita, Kansas
9-23-57

PLUGGING
FILE SEC 31 T 3 R 23W
BOOK PAGE 45 LINE 23