

DISTRICT CONSERVATION AGENT'S REPORT

15-137-00637-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION W¹/₂ W¹/₂ NE

SEC. 31 TWP. 3 RGE. 23

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1~~B~~ Lease Carr-Snead "B"

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Norton

Total Depth 3719 Feet.

Plugging Contractor Farbes Casing Pulling Co

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3091' with 70 sax
cement behind.

Filled with sand to 3080', set 4 sax cement with dump bailer, pulled
3225' 5 1/2" - filled with mud to 250', set rock and 15 sax cement, mud
to 30', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 10-27-54

10-27-54

PLUGGING
FILE SEC 31 T 3 R 23 W
BOOK PAGE 23 LINE 24