

Handwritten mark

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20079-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1972
CONSERVATION DIVISION
Wichita, Kansas
1-21-72

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Herschiser Well No. 1

Location SW-SW-SE Sec. 34 Twp. 3 Rge. (E) (W)23

County Norton Total Depth 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 7:00 PM Day 18 Month 1 Year 1972

The above well was plugged as follows:

334'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Cu. Ft. cement
thru DP from 1200' to 900'. Pulled DP to 330' and displaced 25 Cu. Ft. cement thru
DP from 330' to 260'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 1-21-72
INV. NO. 5050-W