

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/7/04 (Date)
by: Darrel Dipman w/KCC in Hays, KS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
4022-32,4043-47,4076-86,4130-34 Depth to Top: _____ Bottom: _____ T.D. _____
4192-95 Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-153-20,491-00-00
Lease Name: Texaco Cahoj
Well Number: #931
Spot Location (QQQQ): NW - SE - NE -
1650 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 17 Twp. 1 S. R. 34 East West
County: Rawlins
Date Well Completed: 1/19/84
Plugging Commenced: 6/7/04
Plugging Completed: 6/7/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	320'	8 5/8	320	0
	Production	Surface	4360'	5 1/2	4360	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 2500'. RU Swift. Pumped 150 sxs SMD cmt & 500# hulls. Pulled tbg to 1200'. Pumped 65 sxs & 400# hulls. Pulled tbg to 600'. Pumped 35 sxs & 300# hulls & circ cmt to surface. TOH w/tbg. Topped off 5 1/2" csg w/10 sxs & csg stayed full. Hooked onto 8 5/8". Pumped 15 sxs & SI w/300#. Job completed @ 11:30am. Witnessed & approved by Darrel Dipman w/KCC in Hays, KS.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tom W. Nichols
(Address) 250 N. Water, Suite 300; Wichita, KS 67202

RECEIVED
AUG 05 2004
KCC WICHITA



SUBSCRIBED and SWORN TO before me this 4th day of August, 2004
Kristin Grady My Commission Expires: 2/06/08
Notary Public



CHARGE TO: Muffin Drly. Co.
 ADDRESS: _____
 CITY, STATE, ZIP CODE: _____

TICKET No 6954

PAGE 1 OF 1

SERVICE LOCATIONS: Hays, KS
 WELL/PROJECT NO.: 931 LEASE: TEXACO CAH05 COUNTY/PARISH: Hawkins STATE: Ks CITY: _____ DATE: 6-7-04 OWNER: Same
 TICKET TYPE: SERVICE SALES CONTRACTOR: Muffin RIG NAME/NO.: _____ SHIPPED VIA: OT DELIVERED TO: Loc ORDER NO.: _____
 WELL TYPE: Oil WELL CATEGORY: Workover JOB PURPOSE: Plug To Aberdeen WELL PERMIT NO.: _____ WELL LOCATION: _____
 REFERRAL LOCATION: _____ INVOICE INSTRUCTIONS: _____

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT	
		LOC	ACCT	DF								
575		1			MILEAGE #103	120	mil			2.50	300	00
576		1			Pump Service	1	ea			550	550	00
581		1			Service Charge	325	sb			1.00	325	00
583		1			Drayage	1935.6	700 miles			.81	1645	26
330		1			sm oc	275	sb			10.00	2750	00
275		1			Halls	13	sb			20.00	260	00
RECEIVED												
AUG 05 2004												
KCC WICHITA												

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

SIGNED: [Signature] TIME SIGNED: _____
 A.M.
 P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				5,830.26
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				309.00
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL
				6139.26

JOB LOG

SWIFT Services, Inc.

DATE 6-7-04 PAGE NO. 1

CUSTOMER Martin Arls

WELL NO. 9-31

LEASE Chahoc

JOB TYPE Plug To Abandon

TICKET NO. 6954

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0900							On loc. set up truck
	0915							Tubing @ 2500'
								CIBP @ 4060'
			70					Perfs 4022-32, 4043-47
								mix 150 sks SMO with 5 sks Halls
								30 ^{sec} pumped caught press.
								4 BPM 400 psi
	0935							Finished mixing tubing on loc.
								Pull tubing to 1200'
	10:10		30					mix 65 sks SMO with 5 sks Halls
	10:20							Tubing on loc.
								Pull Tubing to 600'
	10:30		15					Mix 3 sks Halls in 35 sks cut
								Circulated to surface
			5					pull tubing out of hole
			7					Pump 10 sks cut. top off 5 1/2" csg.
								Pump 15 sks down Brocken head
								Holding 300 psi
								circulate and pull up truck
								Job Complete

RECEIVED

AUG 05 2004

KCC WICHITA