

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15,137-20,325-00

LEASE NAME Blair

WELL NUMBER #33-1

SPOT LOCATION 50'W NE SW

SEC. 33 TWP. 3 RGE 23 (E) or (W)

COUNTY Norton

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-11-84

Plugging Completed 9-17-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ~~Bell North~~ Bellnorth

ADDRESS ~~Box 249, Woodward, Okla 73801~~

P.O. Box 35288 Tulsa, Okla 74153

PHONE ~~405-256-9525~~ OPERATORS LICENSE NO. 9632

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	352'	None
				4-1/2"	3890'	1787.10

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Found top of cement in casing at 3700'. Shot casing at 2800', 2500', 2250', 2000' and 1800'. Pulled 53 joints of 4-1/2" casing. Halliburton squeezed well with 25 sacks gel with 3 sacks hulls, 100 sacks cement, 15 sacks gel, released plug and pumped 70 sacks 50/50 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 500 psi and shutin 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

SEP 25 1984  
9-25-84  
CONSERVATION DIVISION  
Wichita, Kansas

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 24th day of September, 1984

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

Iona M. Leatherman  
Notary Public

My Commission expires: