

15-137-00702-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Drilled Prior to
ACO-I Inception

API NUMBER _____

LEASE NAME Mindrup

WELL NUMBER #8

SPOT LOCATION C E/2 NW

SEC. 31 TWP. 3S RGE. 23W (W)

COUNTY Norton

Date Well Completed 7-21-54

Plugging Commenced 2-13-84
3:50 P.M.

Plugging Completed 2-13-84
4:45 P.M.

No 2/13 Sent to dist

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE # (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Palco, Kansas (Gilbert Balthazor)

Is ACO-1 filed? -- If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3674' bottom 3680' T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	280'	None
				5-1/2"	3674'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 5-1/2" casing: mixed 15 sks. cement w/1 sk. hulls, released plug, mixed 100 sks. cement @ 500# maximum pressure & shut in. Down annulus: mixed 1 sk. hulls, 2 sks. gel, 50 sks. cement, 3 sks. gel, 60 sks. cement @ 750# maximum pressure & shut in. Came back next day and capped well w/45 sks. cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John O. Farmer, Inc. License No. 5135
Address P.O. Box 352, Russell, KS 67665

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, in the presence of me God.

(Signature) John O. Farmer III
(Address) P.O. Box 352, Russell, KS

SUBSCRIBED AND SWORN TO before me this 1st day of March, 1984

My Commission Expires: January 27, 1985

Margaret A. Schulte
Notary Public
Margaret A. Schulte



STATE CORPORATION COMMISSION
TO BE FILED WITH THE
STATE CORPORATION COMMISSION
OFFICE OF THE SECRETARY
TO BE FILED WITH THE
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
MAR 02 1984
CONSERVATION DIVISION
Wichita, Kansas

7-2