

15-137-00637-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Norton County. Sec. 31 Twp. 3 Rge. (E) 23 (W)

Location as "NE/CNWxSWx" or footage from lines C W/2 NE/4

Lease Owner Jones, Shelburne & Farmer, Inc.

Lease Name Carr-Sneed B Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 10-23 1954

Application for plugging filed 10-18 1954

Application for plugging approved 10-18 1954

Plugging commenced 10-18 1954

Plugging completed 10-23 1954

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 10-1 1954

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3694 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	249	None
				5 1/2	3691	3225

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Circulated heavy rotary mud in hole with cementing truck. Shot casing off at 3225', pulled casing out of hole and plugged well from 3225' to 250'. Set permanent rod bridge. Dumped 15 sacks cement. Filled hole with heavy mud from 210' to 35', dumped 10 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Co.

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

John O. Farmer (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer

Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of November, 1954

My commission expires July 14, 1958

Donnie Pratt  
Notary Public.

PLUGGING  
FILE NO. 31 3 23W  
BOOK PAGE 73 LINE 24

11-5-54