

API NUMBER 15-137-00578-00-00

LEASE NAME Weber

RECEIVED
12-21-01
DEC 21 2001
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 11

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 30 TWP. 3 RGE. 23 (X) or (W)

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

COUNTY Norton

PHONE# 785) 689-4816 OPERATORS LICENSE NO. 5285

Date Well Completed Spud 11/54

Character of Well Oil

Plugging Commenced 10:15A.M. 12/18/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11:00A.M. 12/18/01

The plugging proposal was approved on December 18, 2001 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3796 Bottom 3800 T.D. 3898

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	307'	None
				5 1/2"	3796'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed 260 sx w/200# hulls down 5 1/2". Max psi 800#. Shut in 300#.
Mixed 50 sx down 8 5/8" Max psi 100#. Shut in 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Richard L. Wallgren, Sr. (Employee of Operator) or ~~(Operator)~~ of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Richard L. Wallgren, Sr.
P. O. Box 187, Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 19 day of December xxII 2001



Betty Jane Bittel
Betty Jane Bittel Notary Public

My Commission Expires: July 17, 2004

OR

RECEIVED

DEC 21 2001

WICHITA

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Weber #11
 LOCATION NE NE SE, Sec. 30-3-23W
 POOL NAME Norton COUNTY Norton STATE Kansas
 COMMENCEMENT DATE November 9, 1954 COMPLETION DATE November 15, 1954

LOG OF WELL

Elevation: 2470 R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	307	Shale		
307	750	Shale		
750	1360	Shale-Sand		
1360	1620	Sand		
1620	1630	Shale	0° - 1500'	
1630	1835	Sand-Shale		
1835	2063	Red Bed	0° - 2000'	
2063	2102	Anhydrite		
2102	2190	Shale-Shells		
2190	2590	Lime-Shale	0° - 2500'	
2590	2790	Lime-Shale		
2790	3000	Lime-Shale	0° - 3000'	
3000	3170	Lime-Shale		
3170	3290	Lime-Shale		
3290	3415	Shale-Lime		
3415	3534	Lime-Shale	0° - 3500'	
3534	3605	Lime-Shale		
3605	3670	Lime-Shale		
3670	3725	Lime-Shale		
3725	3795	Lime-Shale		
3795	3798	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 307.20' of 8-5/8" Surface Casing to 307'
 Ran 3796' of 5-1/2" OD Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs
 Office Manager

Subscribed and sworn to before me this 18th day of November, 1954.

My commission expires:
 June 17, 1957

Barbara Donaldson
 Notary Public

RECEIVED
 NOV 20 1954
 G. CUMMINGS