

RECEIVED
AUG 02 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Sutor
WELL NUMBER 1
990 Ft. from S Section Line
330 Ft. from E Section Line
SEC. 30 TWP. 8S RGE. 26 (E) or (W)
COUNTY Sheridan
Date Well Completed 7-27-04
Plugging Commenced 7-27-04
Plugging Completed 7-27-04

LEASE OPERATOR Dreiling Oil, Inc.
ADDRESS Box 550 Hays, KS 67601
PHONE (785) 625-8327 OPERATORS LICENSE NO. 5145

Character of Well Dry Hole
(Oil, Gas, DSA, SWD, Input, Water Supply Well)
If plugging proposal was approved on 7-22-04 (date)

By Herb Dienes (KCC District Agent's Name)

Is ACC-1 filled? No If not, is well log attached? No logs
Producing Formation None Depth to Top _____ Bottom T.D. 4374'

Give depth and thickness of oil water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	236	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

-attached- Well was washed down to plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. Express Well Service License No. 6426
Address Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.

I, Terry Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) Box 550 Hays, KS 67601

Notary Public State of Kansas SUBSCRIBED AND SWORN TO before me this 28th day of July, ~~XX~~ 2004

Patricia Dreiling
My Appt Exp 8-23-06

Patricia Dreiling
Notary Public

My Commission Expires: 8-23-06

SUTOR #1- OWWO
NE SE SE of Section 30-8S-26W
Sheridan County, Kansas

- 7-21-04 Moved in Express Well Service Double Drum Derrick, Mud Pump, Swivel, and Collars. Rigged up. Dug 200 Bbl. Pit. Moved in 2 7/8" Upset Tubing. Put 7 7/8" Bit on collars and began washing down well. Started at 2:00 P. M. At 4:15 P.M. we fell through top plug at 30'. Ran 3 more Drill Collars and stacked out at 90'. Put Swivel back on. Circulated right down to 122'. Ran 4-jts. To 236'. Never hit anything. Pulled tubing, collars and bit.
- 7-22-04 Ran Notched Collar on bottom of 2 7/8" Tubing. Ran in to 540' and stacked out. Put on swivel and began drilling. Got out really heavy mud. Then we started to get wood out of the hole. Got two pieces of fence post about 7" long and some black rubber. (Old style Plug) Made about 10' and began getting just a little cement. Pulled Collar and ran 4 7/8" bit back in the hole. Got to 770.43' and began getting stuck. Tried to get back down 3 times and got stuck each time. Could not get through that point. Went to same point each time. Lots of cuttings. Never lost circulation. Pulled tubing, collars, and bit.
- 7-23-04 Shut down due to rain. 7-24-04 and 7-25-04- Shut down for weekend.
- 7-26-04 Ran in with Notched Collar on bottom of tubing. Stacked out at 745'. Washed down 775' and circulated hole as clean as possible. Getting a lot of cuttings and mud. Began moving down hole slowly. Tried a full joint and circulate but appears to be to heavy to get good circulation. Starting to get decent mud to circulate with. Began washing down 1/2 joint at a time. Got to 1055'. Circulated hole clean and pulled tubing back inside the surface pipe.
- 7-27-04 Ran back to bottom with tubing and stacked out at 697'. Put Swivel on the circulated through 15' Bridge. Once we got through it we went right to 1055'. Finally began moving down the hole. Ran down to 1400' and circulated hole for 1 hour and 15 minutes. Lots of cuttings. Good circulation throughout and good mud in the hole. Spotted 25 Sxs. 60/40 Poz Mix, 6% Gel. At 1400'. Pulled tubing up to 1117' and spotted another 25 Sxs. Of the same. Good circulation throughout. Pulled up to 300' and spotted 40 sxs. Of the same. Pulled up to 40' and circulated the hole full of cement. Pulled last joint. Tore down and moved off. Roger Moses with the KCC was on location to witness. Plug job complete at 2:00 P. M.

RECEIVED
AUG 02 2004
KCC WICHITA

ALLIED CEMENTING CO., INC.

16031

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>7-27-04</u>	SEC <u>30</u>	TWP. <u>8 S</u>	RANGE <u>26 W</u>	CALLED OUT <u>8:00am</u>	ON LOCATION <u>12:40pm</u>	JOB START <u>1:00pm</u>	JOB FINISH <u>2:00pm</u>
LEASE <u>SUTOR</u>	WELL # <u>#1</u>	LOCATION <u>QUINTER 14 N To Redline</u>			COUNTY <u>Sheridan</u>	STATE <u>KANSAS</u>	
OLD OR NEW (Circle one) <u>OLD</u>			<u>1w 4 1/4 N 1/4w into</u>				

CONTRACTOR Express Well Service
 TYPE OF JOB Plug ABANDONED well
 HOLE SIZE _____ T.D. _____
 CASING SIZE 8 5/8 DEPTH 237'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER "Same"
 CEMENT AMOUNT ORDERED 100 SK 69 40 6% gel
 COMMON _____ @ _____
 POZMIX _____ @ _____
 GEL _____ @ _____
 CHLORIDE _____ @ _____
 ASC _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER Glenal
 # 366 HELPER Shane
 BULK TRUCK DRIVER RUFUS
 # 362 DRIVER _____
 BULK TRUCK DRIVER _____
 # _____

RECEIVED
 AUG 02 2004
 KCC WICHITA
 HANDLING _____ @ _____
 MILEAGE _____ @ _____
 TOTAL _____

REMARKS:

25 SK @ 1400'
25 SK @ 1117'
40 SK @ 300'
10 SK @ 40'

THANKS

CHARGE TO: DREILING Oil Co.
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____
 EXTRA FOOTAGE _____ @ _____
 MILEAGE _____ @ _____
 TOTAL _____

PLUG & FLOAT EQUIPMENT

MANIFOLD _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME