

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #: n/a
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-30-04 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2761' Bottom: 2773' T.D. _____
Toronto Depth to Top: 2837' Bottom: 2840' T.D. _____
LKC Depth to Top: 2932' Bottom: 3057' T.D. 3192'

API Number: 15-167-05489-00-00
Lease Name: Kaufman B
Well Number: #4
Spot Location (QQQQ): S/2 - SW - SW -
330 Feet from North / South Section Line
4620 Feet from East / West Section Line
Sec. 22 Twp. 15 S. R. 12 East West
County: Russell
Date Well Completed: 7-30-47
Plugging Commenced: 4-21-04
Plugging Completed: 4-21-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0'	673'	10 3/4"	673'	0'
Production		0'	3187'	5 1/2"	3187'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 1335' and 723'. Fluid at approximately 1500'. Tied onto 5 1/2" and pumped 165 sx 60/40 Pozmix, 10% gel w/600# hulls. Max PSI 400#, SIP 100#. Pumped 35 sx cement into annulus. Max PSI 300#, SIP 100#.

RECEIVED

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

AUG 02 2004

Address: P.O. Box 466, Ness City, KS 67560-0466

KCC WICHITA


Name of Party Responsible for Plugging Fees: Gore Oil Company

State of Kansas County, Sedgwick, ss.

Larry M. Jack

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack
(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 29th day of July, 20 04

Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]