

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-24291-0000

LEASE NAME Delma

WELL NUMBER 1

2,250 Ft. from S Section Line

2,025 Ft. from <sup>W</sup>~~X~~ Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hutchinson Oil Co.

ADDRESS PO Box 521, Derby, KS 67037

PHONE (316) 788-5440 OPERATORS LICENSE NO. 5,614

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-28-04 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4,420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	235'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 1,600', pump 50 sax cement on plug thru drill pipe. Push bridge plug to 800', pump 50 sax cement on plug thru drill pipe. Push bridge plug to 250', pump 50 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 15 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5,184

Address PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hutchinson Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~operator~~) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 30th day of July, ~~2004~~ 2004

Ruth Phillips  
Notary Public

My Commission Expires:



RECEIVED  
AUG 04 2004  
KCC WICHITA