


All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Norton County. Sec. 29 Twp. 3 Rge. 23 (E) (W) X
Location as "NE/CNW/SW" or footage from lines W 1/2 W 1/2 NW
Lease Owner D. G. Hansen
Lease Name Cope Well No. # 6
Office Address Box 187, Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 1-31-63 19____
Application for plugging approved _____ 19____
Plugging commenced 2-8-63 19____
Plugging completed 2-14-63 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3751' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3740', mixed and ran 4 sacks cement thru dump bailor.
Pumped plug to 3000' by Sun Oilwell Cementing
Pulled 78 joints, circulated hole with 15 sacks gel and spotted 20 sacks cement at 500'. Pulled 8 joints and spotted 20 sacks cement at 240. Pulled 8 joints.
Mudded hole to 40' and sat 10' rock bridge, mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1963
2-18-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer - Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of February, 19 63

My commission expires 24 October 1964
Sidney D. Miller Notary Public.

INVOICED
DATE 2/18/63
INV. NO. 6602-W

15-137-00695-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Cope Well #6
LOCATION The approximate Center of the West Line of the NW/4 Sec. 29-3-23W
POOL NAME Norton COUNTY Norton STATE Kansas
COMMENCEMENT DATE March 5, 1955 COMPLETION DATE March 13, 1955

LOG OF WELL

Elevation: 2414 Rotary Bushing
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION From VERTICAL	REMARKS:
0	276	Shale-Shells		
276	680	Shale		
680	1480	Shale-Sand		
1480	2008	Shale-Shells	0° - 1500'	
2008	2040	Anhydrite	0° - 2000'	
2040	2405	Shale-Lime		
2405	2605	Shale-Lime	0° - 2500'	
2605	2740	Lime-Shale		
2740	2920	Lime-Shale		
2920	3020	Lime-Shale	0° - 3000'	
3020	3140	Lime-Shale		
3140	3310	Lime-Shale		
3310	3415	Shale-Lime		Lost circ. @ 3343'
3415	3490	Shale-Lime		
3490	3570	Lime-Shale	0° - 3500'	Lost circ. @ 3514'
3570	3655	Lime-Shale		Lost circ. @ 3573'
3655	3739	Lime-Shale		
3739	3742	Lime-Shale		DST 3736-3739
				DST 3736-3742
3742	3746	Lime-Shale		DST 3736-3746
3746	3750	Lime-Shale		DST 3744-3750

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1963
2-29-63
CONSERVATION DIVISION
Wichita, Kansas

CASING LEFT IN HOLE AFTER COMPLETION

Ran 276.20' (9 jts.) 8-5/8" OD Surface Casing.
Set 3735.53' (116 jts.) 5-1/2" OD Production String of Casing.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By R. G. Cook, Partner

SUBSCRIBED and sworn to before/this 15th day of March, 1955.

My commission expires:
June 25, 1955

W. J. [Signature]
Notary Public