

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-137-30102-00-00

RECEIVED  
OCT 3 1966  
10-03-1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bill Hubbell,

Complete Address: 706 Union Center, Wichita, Kansas.

Lease Name Horesky Well No. 1

Location CNE-NW Sec. 15 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3680'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00PM Day 27 Month 9 Year 1966

The Above well was plugged as follows:

224'--8 5/8" Surface pipe, cement circulated.

3678'--5 1/2" Production casing cemented with 125 Sx. Top perforations from 3640' to 3646'.

Sanded well back to 3620' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" set rock and sand bridge from 450' to 405' and filled hole to bottom of cellar with Redi-Mix cement. (Used 5 1/2 yards)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 10/3/66  
INV. NO. 4034-W