

DISTRICT CONSERVATION AGENT'S REPORT

*B*

TO:

15-137-00062-00-00

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 12 TWP. 3 RGE. 23

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Muir

Operator Great Lakes Carbon Address 501 Bet Bldg Wichita,

Field \_\_\_\_\_ County Norton

Total Depth 3722 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 218' circulated with cement.

Filled hole with heavy rotary mud to 200', set cementing  
plug, 1/2 sack hulls and 15 sax cement, rotary mud to 40',  
set cementing plug, 1/2 sack hulls and 10 sax cement to  
bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
07-09-1951  
JUL - 9 1951  
CONSERVATION DIVISION  
Wichita, Kansas

*Edwin Lee*  
District Conservation Agent

Date 7-4-51

**PLUGGING**  
FILE SEC 12 T 3 R 23  
BOOK PAGE 92 LINE 14