

KANSAS

Form CP-3
Rev. 6-26-62

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-137-20003-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1967
06-23-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rockford Mineral Products, Incorporated,

Complete Address: 206 So. State St., Rockford, Illinois.

Lease Name Harrison Well No. 1

Location NE-NW Sec. 11 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3678

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Vaughan Drilling, Incorporated,

Address: Box #825, Great Bend, Kansas. License No.

Operation Completed: Hour 9:00AM Day 21 Month 6 Year 1967

The Above well was plugged as follows:

241'--8 5/8" Surface pipe, cement circulated with 185 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 240', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichol*
Well Plugging Supervisor

DATE 6/27/67
INV. NO. 5476-W
552-W