

15-137-30073-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

*7*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 1967  
04-03-1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Oil Property Management, Incorporated,

Complete Address: 300 Insurance Building, Wichita, Kansas.

Lease Name Henderson Well No. B-1

Location NW-NW-NW Sec. 10 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth Knight Casing: 3548'  
Plugging Auth: 3548'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 346

Operation Completed: Hour 7:00PM Day 27 Month 3 Year 1967

The Above well was plugged as follows:

160'--8 5/8" Surface pipe, cement circulated.  
3537'--5 1/2" Production casing cemented with 50 Sx. No perforations, open hole completion.

Sanded well back to 3530' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well with 33 sacks gell using 5 sacks hulls in initial gel and followed with 75 Sx. cement. Max. pump--in pressure 400#. Final shut-in pressure 150#. (Recovered 2023' 5 1/2" Csg.).

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/3/67  
INV. NO. 4992-W

Signed: W. L. Nichols  
Well Plugging Supervisor