

R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-137-30000-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965
01-11-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward and March Drilling Company,

Complete Address: 531 Petroleum Building, Wichita, Kansas.

Lease Name Shelton Well No. 1

Location CNE-SW Sec. 4 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3625

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: March Drilling Company,

Address: 531 Petroleum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 5:00PM Day 6 Month 1 Year 1965

The Above well was plugged as follows:

160'--8 5/8" Surface pipe, cement circulated with 140 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 155', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-12-65

INV. NO. 512-W

Signed: H. L. Dechals
Well Plugging Supervisor