

15-137-19012-00-02

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Glen N. Rupe,

Complete Address 222 Brown Building, Wichita, Kansas.

Lease Name Derks Well No. 1

Location CNW-SE, Sec. 4 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3578'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 6:00 PM Day 10 Month 10 Year 1969

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 185 Sx.  
3577'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back or perfor-  
ations indicated.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well with initially 5 sacks hulls and 15 sacks gel and followed with  
100 Sx. cement from 1000' to 675' then 11 sacks gel from 675' to 235' and followed  
with 25 sacks cement from 235' to 160' then 4 sacks gel from 160' to 15' and finally  
5 Sx. cement from 15' to bottom of cellar. Maximum pump-in pressure--900#. Final

Shut-in pressure--200#. (Recovered 1500' 5 1/2" casing). Mudding and cementing opera-  
tions by Globe Cementing, Inc.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 10/13/69  
INV. NO. 639-U

Signed: M. L. Nichols  
Well Plugging Supervisor