

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1967  
07-06-1967  
CONSERVATION DIVISION  
Wichita, Kansas

20004  
15-137-~~3004~~-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Leonard Williams of Vaughan Drilling, Inc., has this

date requested permission to plug the following described well:

R. P. Nixon Operations, Inc.

Mr. Willaims guarantees payment of the plugging fee.

Operator's full Name: R. P. Nixon Operations, Incorporated,

Complete Address: 745 East Wichita Avenue, Russell, Kansas.

Lease Name: Shelton Well No. 1

Location: SE-SE-SW Sec. 20 Twp. 3 Rge. (E)(W) 23

County Norton Total Depth 3725 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Williams was instructed to plug the well as follows:

263'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"	"	280'	with $\frac{1}{4}$ sk. hulls &
			20 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement.

Very truly yours,

A. L. Pichel  
Conservation Division Agent