

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-137-20004-00-00

JUL 6 1967
07-06-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name NIXON
R. P. Nixon Operations, Incorporated,

Complete Address: 745 East Wichita Avenue, Russell, Kansas.

Lease Name Shelton Well No. 1

Location SE-SE-SW Sec. 20 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3725

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Vaughan Drilling, Incorporated,

Address: 1618 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 8:PM Day 3 Month 7 Year 1967

The Above well was plugged as follows:

263'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx. cement

thru DP. Heavy mud to 280', set plug with 1/2 sack hulls and displaced 20 Sx.

cement thru DP. Heavy mud to 40', wet plug with 1/2 sack hulls and 10 Sx.

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 7/6/67
INV. NO. 5531-14