

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-137-20230-00-01

API Number 15- (OWWO)

~~15-20230-00-01~~

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name CANADIAN OIL CORPORATION

Complete Address 710 PETROLEUM BLDG., WICHITA, KANS. 67202

Lease Name BRANSON Well No. #1

Location SE-SW Sec. 19 Twp. 3 Rge. 23 (East)(West)

County NORTON Total Depth 2339 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated OWWO X (OWWO) ABANDONED

Plugging Contractor MURFIN DRILLING CO. (ED McHENNA)

Address 617 UNION CENTER, WICHITA, KANS. 67202 License No. _____

Operation Completed: Hour: 1:30 A.M. Day: 12th Month: AUG. Year: 19 82

Plugging Operations attended by Agent?: All Part None X

The above well was plugged as follows:

8 5/8" - 260 FT SP. CUP.

THIS WELL WAS A WASH DOWN - THEY WENT OUT OF THE HOLE @ 1250 FT. ALSO GOT BIT STUCK ON A TRIP @ 2000 FT.

DECIDED TO ABANDON AND PLUG, NO CIRCULATION PROBLEMS. ORDERED 160 ST 50 FORMIX 4% GEL - 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1ST PLUG @ 1200 FT ST 80 CMT, → 2ND PLUG @ 300 FT ST 50 CMT.

3RD PLUG → ^{SOLID BRIDGE} HULL'S - PLUG @ 40 FT ST 10 CMT, → 10ST IN RAT HOLE (AIR).

Amount of Surface Casing: 260 FT. 10ST IN MOUSE HOLE (AIR)

CEMENTED BY HALLIBURTON

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Martin J. Shredt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
08-23-1982
AUG 25 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE: 9-2-82
INV. NO.: 1005-W